

Site Control Philosophy — Meadowbank

Dispatch and curtailment logic

Priority 1: export available PV up to the 15 MW firm limit.

Priority 2: charge the BESS from surplus PV above the firm limit.

Priority 3: discharge the BESS into the evening peak within the firm limit. The controller responds to DNO ANM curtailment signals within two seconds.